

CITY OF AKRON NOTES

PERMIT INSPECTION NOTES

1. CALL 330-375-2055 TO NOTIFY AND SCHEDULE FOR MANDATORY INSPECTIONS 48 HOURS BEFORE WORK IS TO BEGIN IN THE RIGHT-OF-WAY.
2. ALL PAVEMENT, CURB, AND SIDEWALK TO BE REMOVED SHALL BE SAW CUT FULL DEPTH AT EXISTING CONSTRUCTION JOINTS.
3. ALL SAW CUTTING MUST BE DONE WET, TO CONFORM TO THE OHIO EPA'S FUGITIVE DUST ACT.
4. NO WIRE OR REBAR IN THE CONCRETE WITHIN THE CITY OF AKRON RIGHT-OF-WAY.
5. DOWNSPOUTS SHALL BE INSTALLED TO CONFORM WITH CITY OF AKRON STANDARD DRAWING S-2.
6. ALL RESTORATION WITHIN THE CITY OF AKRON RIGHT-OF-WAY MUST BE COMPLETED TO THE AKRON ENGINEERING BUREAU'S MOST UP TO DATE CONSTRUCTION AND MATERIAL SPECIFICATIONS (CMS) AND STANDARD DRAWINGS.
7. CMS AND STANDARD DRAWINGS ARE LOCATED AS www.akronohio.gov/engineering

WATER DISTRIBUTION

1. PROPOSED WATER SERVICE, METER AND INSPECTION FEES ARE PAYABLE AT THE CITY OF AKRON PLANS AND PERMITS CENTER, 1030 E. TALLMADGE AVENUE.
2. ALL UNDERGROUND STRAIGHT LENGTHS OF PIPE LARGER THAN 2 INCHES SHALL BE CLASS 53 CEMENT LINED DUCTILE IRON WITH PUSH-ON JOINTS AND ALL 2 INCH AND SMALLER PIPING SHALL BE TYPE K COPPER. PIPE SHALL BE INSTALLED WITH 4 FEET 6 INCHES OF COVER. SEE DETAILED SPECIFICATIONS FOR WATER LINE NOTES, APPROVED PIPE, FITTINGS, BOLTS, ETC., AND TYPICAL CONCRETE THRUST BLOCKING (2017-009-02, 03 AND 19).
3. CONTACT TOMMY BARNETT FOR A MANDATORY UNDERGROUND WATER LINE INSPECTION PRIOR TO BACKFILLING THE TRENCH AT (330) 812-7822.
4. CONTACT THE UTILITIES BUSINESS OFFICE AND ASK FOR "NEW SITES" TO HAVE YOUR ACCOUNT SETUP AND HANDLE ANY NECESSARY BILLING PAPERWORK AT (330) 375-2554.
5. ONCE PAYMENT IS MADE, CONTRACT THE METER SHOP TO SCHEDULE PICKUP OF PROPOSED WATER METERS AT (330) 375-2443.
6. AT THE WATER ENTRY POINT DETAILS ARE AVAILABLE ONLINE AT www.akronohio.gov/water THEN SEE THE LINK TO THE RIGHT FOR AWS STANDARD DRAWINGS.
7. ONCE THE METER SETTING IS CONSTRUCTED AND BACKFLOW PREVENTION ASSEMBLIES ARE INSTALLED, CONTACT MELISSA LONGFELLOW TO SCHEDULE A MANDATORY INSPECTION AT (330-)375-2690.

SEWER MAINTENANCE

1. WATER SERVICE MUST MAINTAIN A MINIMUM HORIZONTAL SEPARATION OF 10 FEET FROM THE SANITARY SEWER LATERAL.
2. SANITARY AND STORM SEWER MATERIALS IN THE RIGHT-OF-WAY ARE REQUIRED TO MEET THE AKRON ENGINEERING BUREAU'S MOST UP TO DATE CMS AND STANDARD DRAWING SPECIFICATIONS.
3. CMS AND STANDARD DRAWINGS ARE LOCATED AT www.akronohio.gov/engineering
4. CONTACT JOE HARBESON WITH SEWER MAINTENANCE 48 HOURS IN ADVANCE FOR MANDATORY INSPECTIONS, 330-375-2666.
5. ANY PROJECT STARTING AFTER JUNE 1, 2021, THE CITY REQUIRES THE CONTRACTOR TO VIDEO EXISTING CONDITIONS PRIOR TO STARTING WORK. TELEVISED VIDEO RECORDING OF ALL SEWERS AND LATERALS THAT ARE WITHIN 100' OF TRENCHING OR TRENCHLESS EXCAVATIONS IS REQUIRED BEFORE AND AFTER WORK. PRE- AND POST-CONSTRUCTION VIDEOS ARE REQUIRED TO BE PROVIDED TO THE CITY FOR IT'S RECORD KEEPING.

ADD THE FOLLOWING NOTES IF FOOD SERVICE BUSINESS OF HAVE A COMMERCIAL KITCHEN

- ALL GREY WATER PLUMBING WITH THE ACCEPTATION OF RESTROOMS ARE REQUIRED TO BE PLUMBED THROUGH THE GREASE INTERCEPTOR
- CITY OF AKRON 1000 GALLON GREASE INTERCEPTOR TO BE INSTALLED
- CITY OF AKRON 1000 GALLON GREASE INTERCEPTOR CAN BE FOUND AT <https://www.akronohio.gov/cms/site/FOG/index.html>

STORM WATER POLLUTION PREVENTION PLAN (SWPPP)

1. PROJECTS THAT HAVE AN AREA OF (1) ACRE OR MORE IN DISTURBANCE REQUIRE SUMMIT SOIL AND WATER CONSERVATION DISTRICT APPROVAL.
2. SILT FENCE IS REQUIRED TO SURROUND THE PROJECT AREA TO KEEP SEDIMENT FROM LEAVING THE PROJECT SITE INTO THE PUBLIC RIGHT-OF-WAY, ADJOIN PROPERTIES, STREAMS, RIVERS, PONDS, LAKES, OR SEWERS.
3. INLET PROTECTION MUST BE PROTECTED ACCORDINGLY TO THE TYPE OF INLET, AND INSTALLED AND IN PLACE BEFORE CONSTRUCTION IS TO BEGIN.

4. SITE SPOILS MUST BE SURROUNDED WITH SILT FENCE UNTIL REMOVED FROM SITE OR 75% OF STABILIZATION VEGETATION HAS GROWN.
5. CONCRETE WASH OUT LOCATION MUST BE LOCATED ON SITE TO COLLECT ALL CONCRETE AND MORTAR EXCESS AND EQUIPMENT CLEAN UP.
6. ALL WASH OUT AND EXCESS CONCRETE AND MORTAR WILL BE CLEANED UP AND REMOVED FROM THE PROJECT SITE AND DISPOSED OF IN PROPER MANNER.

GUTTERS AND DOWNSPOUTS

1. GUTTERS AND DOWNSPOUTS ARE NOT PERMITTED TO DRAIN OVER THE GROUND.
2. THEY MUST BE CONNECTED TO THE FOLLOWING IN ORDER OF PREFERENCE:
 - a PUBLIC STORM SEWER.
 - b COMBINATION SEWER.
 - c STREET GUTTER OR DITCH.
 - d NATURAL DRAINAGE WAY (STREAM OR RIVER).
 - e LEACH WELLS SIZED FOR ONE CUBIT FOOT OF WASHED GRAVEL PER FIFTEEN SQUARE FEET OR ROOF AREA, UNLESS DESIGNED BY A REGISTERED PROFESSIONAL ENGINEER.
3. DOWNSPOUTS ARE NOT ALLOWED TO BE TIED DIRECTLY INTO CATCH BASINS/ INLETS.